


# **LWRS Spring Review**

Flexible Plant Operation and Generation (FPOG)

Richard Boardman, Pathway Lead April 30, 2024



# FPOG enables diversification of light-water reactors to produce non-electrical products



## **FPOG Research Emphasis**

### Technical & economic assessments

- Hydrogen production using water-splitting electrolysis
- Hydrogen markets; current and emerging
- Thermal energy extraction, storage, and delivery to Industry


### Dynamic energy offtake and delivery to the second user

- Steam diversion and transport to a close-coupled industry
- Electrical energy offtake in front of the grid
- New control concepts and human factors

# Safety hazards and regulatory review research

- Fire and explosion hazards analysis
- New risk initiating events
- Probability risk assessments
- Operating license review

Levelized cost of hydrogen is competitive for markets that value clean energy products; power, fuels, chemicals, steel



Nuclear plants can contribute to meet DOE's goal of producing H<sub>2</sub> for <\$2/kg





## **FPOG Progressive R&D Stages**

Architecture/Engineering design for heat and power delivery to hydrogen plants

Detailed 100, 500, & 1000 MW hydrogen plant design and updated PRA for generic power plant

2019: Full Technical & Economic Analysis for nuclear plants in Upper Midwest Region

2018: H2@Scale analysis for Exelon, Xcel, & So. Company

- Initiated FPOG/Industry stakeholder meetings
- Completed first H<sub>2</sub>
   production technical and
   economic evaluation
- Developed approach for nuclear-H<sub>2</sub> risk assessments
- Began FPOG thermal dispatch operations testing

- Began electrolysis module testing and confirmed H, plant designs and production cost assumptions
- Developed full-scope simulators for PWR/H, plants operations testing
- Completed preliminary PRA for H, production
- Expanded utility outreach

- Completed preconceptual mechanical and electrical connections design for a 100 MW, steam electrolysis plant
- Began industy supported FPOG control concepts demonstration
- Established a hydrogen regulator review research group (H3RG)
- Evaluated FPOG energy storage options

- Completed preconceptual mechanical and electrical connections design for a 500 MW, steam electrolysis plant
- Completed detailed hazardous analysis for electrolysis plant
- Updated preliminary PRA using conceptual design and FMEA
- Started H<sub>2</sub> production at Nine Mile Point Nuclear Station

2020 2021

2022

2023

### **FY-24 Task Highlights:**

- Capstone on hydrogen production with nuclear power plants
- Assessment of Gulf Shore hydrogen and thermal markets
- □ Prospector tool for screening FPOG markets
- □ Value of nuclear power plants relevance to grid reliability & resilience
- □ 30-50-70% thermal energy offtake designs and concepts of operations



# **Industry Engagement**

- ☐ Electric Power Research Institute / Nuclear Beyond Electricity
- □ Cost-shared Industry Funded Research
  - Hydrogen market studies
  - Electrolysis hydrogen demonstration projects
  - Co-electrolysis technology testing
  - Control systems and thermal energy offtake development
  - Full-scope simulator development for nuclear-hydrogen coupled plants
  - Bloom Energy electrolysis module testing, including flexible ramping up and down from 10% to 95% of full power
- ☐ Hydrogen Hub Projects


























# Calculator for utility-scale hydrogen production market potential analysis



## Foundational Laboratory R&D Efforts

Controls systems and user interfaces

Human factors development and operator performance testing



Full-scope licensed operator simulation in Human System Simulation Lab (HSSL)



Real hardware and grid simulations










Bloomenergy





# Nuclear Power Plant Simulators Ready for Development of Operating Concepts for FPOG

- LWRS leads completed the installation and verification of full-scope simulators of a nuclear plant coupled to a high temperature steam electrolysis plant.
  - GSE was contracted to modify a simulator for a pressurized-water reactors and a boiling water-reactors based on an architecture/engineering preconceptual design for thermal and electrical coupling to a hydrogen plant
  - Westinghouse Cooperative Research and Development Agreement and contract supporting development of operating concepts and full-scope simulators based on a pressurized-water reactor
  - A dynamic model for the electrolysis plant was added to the plant simulator to provide realistic feedback to plant operators regarding the status of the hydrogen plant
  - Both simulators were installed and verified at the INL Human Systems Simulation Laboratory
- The modified simulators are being used to test operating concepts, address human factors, and prove NPP operators can reliably and safely dispatch thermal and electrical power to a hydrogen plant



GSE Systems Inc. Modified Boiling Water Reactor in the Human Systems Simulation Laboratory

Contact thomas.ulrich@inl.gov or tyler.westover@inl.gov for more information

# **Conceptual Design Development**


Electrical and thermal integration modeling of co-located HTE at a Standard 1200 MW NPP


Traditional engineering methods used to limit uncertainties on design and operational impacts

Failure Modes and Effects Analysis (FMEA) input to risk modeling

Generic design evaluated under 10 CFR 50.59 process









# Risk Analysis Approach Progression

Early simplified probabilistic risk assessment (PRA) approaches

Initiating events, fault trees, FMEA addressed

Steam rupture, fire, explosion, and other hazards evaluated for plant operating modes

Qualitative hazards assessment for potential community and utility business risks

Evaluation of offset distances to H2 plant from NPP critical infrastructure











Computer-Aided Fault Tree Analysis (CAFTA)





# Hazards and Probabilistic Risk Assessments of a LWR Coupled with Electrolysis Utility-Scale Hydrogen Production Plants

### INL/RPT-23-74319 issued August 30, 2023

- Detailed 100, 500, and 1000 MW<sub>nom</sub> HTE hydrogen production facilities
- Defined thermal extraction systems for each size of hydrogen plant
- Determined safe unbarriered standoff distances for each section of the plant
- Applied facility layouts and standoff distances to common generic sites of nuclear power plants
- PRA model calculated the increased initiating event frequencies and other metrics required for NRC licensing acceptance

Turbine Building

Turbine Buil



Hypothetical Nuclear-Powered Hydrogen Plant located near community area


# Heat Balance Model Analysis and Equipment Assessment for 30%, 50% and 70% Thermal Power Extraction from a Nuclear Plant

#### INL/RPT-24-772067 issued March 2024

- Engineering assessment of the impacts to the PWR secondary system based on PEPSE model results for the respective thermal power delivery scenarios.
- Evaluate impacts of thermal and mechanical stresses associated with thermal power extraction on nuclear plant components:
  - High- and low-pressure turbines, main condenser, power train pumps, moisture separator reheaters, drain systems, feedwater heaters, and extraction steam equipment, etc.

#### **Conclusions:**

- A nuclear plant can reasonably accommodate up to 50% thermal power extraction without significant impact
- 70% thermal energy extraction presents challenges for the secondary plant and the nuclear steam supply system



# Pilot Plant Hydrogen Production Demonstration Projects

### □ Technical:

Addressed by beta prototype and systems verification testing

### □ Economic / Business:

Beta prototype testing for Front-End Engineering Design study; Engineering & Plant Construction Design, Capital & Operating Costs; Warranty

### □ Permitting:

Safety hazards; Emissions verification; Risk assessments; NRC Licensing



## Constellation: Nine-Mile Point Plant

- H<sub>2</sub> production began in 2023
- Nel proton electrolyte membrane (PEM) electrolysis module



**Xcel Energy:** Prairie Island Plant

- H<sub>2</sub> production beginning in 2024
- Bloom Energy high temperature solidoxide electrolysis cell (SOEC) module



Vistra:
Davis-Besse Plant

- H<sub>2</sub> production beginning in 2024
- PEM or SOEC electrolysis unit

### EERE R 540.112 02: Technology Readiness Levels (TRLs)

**TRL-6.** System/process model or prototype demonstration in a relevant environment-Beta prototype (system): Prototyping implementations are partially integrated with existing systems. Engineering feasibility fully demonstrated in actual or high-fidelity system applications in an environment relevant to the end user.





# **Sustaining National Nuclear Assets**

Richard.Boardman@inl.gov

*lwrs.inl.gov*