

# Human and Technology Integration

A Dominion/INL Joint Effort

## Dominion's Plant Modernization Activities:

Human Factors Multi-Stage Validation Lesson Learned

Stephen J. Kenney, Contractor  
Human Factors Consulting SME  
BCP Engineers & Consultants

# The Plan

Begin with the end in mind – designing the end state



SPS



NAPS

## Phased Evolution

5 sequential outages





CV




PV



ISV





# Process Flow Illustrated











# HFE Program, V&V Focus

NUREG-0711 Rev. 3,  
Figure 7-1

NUREG-0711 Rev. 3, Figure 1-1



# Multi-Stage Validation Environments

3D Models	Photo Mosaics	Human Factors Engineering Grade Simulator (HFEES)	Glass Panel Main Control Room Simulator (GPMS)	Plant Reference Simulators
<b>Surry</b> 				
<b>North Anna</b> 		<p>No HFEES</p>	<p>Planned GPMS</p>	

# Validation Workshops

## Conducted to Date




- SPS Phase 0/1A CV
- NAPS/SPS ICCM CV
- NAPS Rod Control CV
- SPS Phase 0/1A PV
- NAPS Phase 0 CV

## Planned

- SPS CVs Phase 1B ...
- SPS PVs Phase 1B ...
- SPS ISVs Phase 0/1A
- NAPS CVs Phase 1B ...
- NAPS PVs Phase 0/1A ...
- NAPS ISVs Phase 0/1A ...

## Acronyms

- CV = Conceptual Validation
- ISV = Integrated System Validation
- NAPS = North Anna Power Station
- PV = Preliminary Validation
- SPS = Surry Power Station



# ISV Environment

- Guidance states use Plant Reference Simulator (PRS)
- Availability of PRS due to Operator License examinations
- Time to complete PRS modifications and execute the ISV before plant implementation
- Use of alternate environments (ANS-3.5.1)

# Lessons Learned (so far)

## Planning

- Identify potentially affected Important Human Actions (IHAs) ASAP
- Develop scenarios using a cross-discipline team and available resources (e.g., Ops, design engineers, HFE, safety analysis, procedures, training, sim support, NUREG-0711 Appendix A)
- Leverage prior NRC submittals for report content/presentation to set up workshop plan

## Preparing the Environments

- Plan Ops resources well in advance to find available windows to conduct workshops
- Understand resource needs for graphics development and programming
- Install, prepare, and test quality A/V tools before conducting workshops
- Develop appropriate draft procedures for demonstration



# Lessons Learned (so far – cont.)

## Executing the Workshop

- Set up observation collection aligned with report presentation
- Clarify feedback at the end of each day to pinpoint issues, what is affected, and who to contact for additional information
- Involve key stakeholders to increase awareness of the changes, quality of implementing actions, and receiving organization ownership
- Dedicated support is needed for the overall coordination of the multiple concurrent activities (before, during, and after)
- Collect and implement process improvements after each stage
- IEEE-2411 Multi-Stage Validation works (so far)

# Summary

- Dominion is the 1<sup>st</sup> U.S. utility planning full Control Room Modernization as part of its Subsequent License Renewal program
- Dominion is evolving its Control Room Modernization Process using best available information (internal and external)
- Dominion is leveraging its relationship with INL (CRADA) and other industry groups to address HFE challenges
- Opportunities for collaboration
  - Qualification of simulation environments (ANS-3.5.1, PWROG)
- Achieving Control Room Modernization as part of the SLR program extending by 20 years the life of the 4 nuclear plant assets will contribute to the Sustainability of these Carbon Free Processes

# Questions?